

N. Gilbert Street Reconstruction Project

Public Meeting No. 1

November 16, 2022









Introduction



Josh Straka, P.E. – Strand Associates

Consultant Engineer hired by City for Design Services



Tyler Olson, P.E. – Iowa City

Engineer from City – Project Manager 410 E. Washington Street Iowa City, IA 52240

Office: (319) 356-5416

tolson@iowa-city.org

The Story

N Gilbert Street requires Full Reconstruction due to:

- Street pavement condition
- No storm sewer for most of the street section
- Aging sanitary sewer

This Reconstructed Street should implement City's Complete Streets Policy as much as possible


- In Summary: The Vision of the Complete Street policy is to realize long-term cost-savings and, among other things, to have walkable neighborhoods, create a sense of community pride, and improve quality-of-life
- Complete Street is defined as a street that accommodates convenient and safe use by everyone, regardless of age, ability, or mode of travel.





What is proposed for Construction?


Project is still in the early phase and may revise improvement item inclusion with the project as the project progresses. Priority items for improvements include (in no particular order):





addition of pedestals and/or other utility

infrastructure.












What are the Benefits?


Project is still in the early phase and may revise improvement item inclusion with the project as the project progresses. Generally, benefits for improvements include (in no particular order):














What is the Overall Project Schedule?







Existing Field Survey (End of Fall)



Alternatives Research and Concept Review (End of Fall)



Public Meeting No. 1 (End of Year)



Preliminary Concept Selected (End of Year)

2023



If needed, any Property Acquisition and/or Easement Agreements
Completed (2024)



Private Utility Undergrounding (Summer 2023 thru Fall 2024)



Preliminary Design Plan (End of Summer)



Public Meeting No. 2 (End of Fall)



Final Design (End of Year)



Contractor Bidding (2024)

<u>2025</u>



Pre-construction Public Meeting (Late Winter / Early Spring)



Begin Construction (Spring)



Complete Major Construction Activity (End of Fall)



As-Built Field Survey (End of Fall)



Complete Seeding and Planting Restoration Work (End of Fall 2025 and if needed, may extend into Spring of 2026)

Please note this schedule is an estimated timeline.
It may change as the project develops.

What are some Conflicts

Existing Width of Public Right-of-Way

Public Right-of-Way: Property dedicated to the public use and intended for the movement of the public, including utilities.


Need space for:

- Street
- Parkway
- Sidewalks
- Utility Access

Existing Condition Challenges

Existing Items:

- Retaining Walls
- Trees
- Sidewalks
- Fences
- Steep Roadway Grades
- Steep Driveways vs. Flat Driveways on Opposite Sides of the Roadway



Example of Potential Conflicts

















Concept Alternatives

Altornative 1

- Utilizes existing public right-of-way
- 22-feet wide concrete street with curbs
- 4-feet wide sidewalks on both sides of the street with passing area to meet ADA requirements
- No on-street parking
- Relatively limited conflicts with existing plantings, walls, and fences.

Altornative 2

- Utilizes existing public right-of-way
- 26-feet wide concrete street with curbs
- 4-feet wide sidewalks on both sides of the street with passing area to meet ADA requirements
- Allows alternating ODD or EVEN day on-street parking
- Likely more conflicts than Alternatives 1 for existing plantings, walls, and fences.

Questions?

If you later have any questions, please reach out to:

Tyler Olson, P.E. – Iowa City

Engineer from City – Project Manager 410 E. Washington Street Iowa City, IA 52240 Office: (319) 356-5416

tolson@iowa-city.org

If you have not already, please fill out the attendance sheet before you leave.

Thank you!